

BOREXINO AT GRAN SASSO

A STATUS REPORT

GIOACCHINO RANUCCI

NO - VE

VENEZIA JULY, 24, 2001

SUMMARY

- DESCRIPTION OF THE DETECTOR
- PHYSICS PROGRAM - IMPACT OF SNO RESULTS
- RADIOPURITY ISSUES
- STATUS OF THE INSTALLATION
- CONCLUSIONS

Borexino Collaboration

✓ Belgium

I.R.M.M. European Joint Research Centre - Geel

✓ France

College de France

✓ Germany

Max-Planck-Institut Für Kernphysics Heidelberg
Technische Universität München

✓ Hungary

KFKI-RMKI Budapest

✓ Italy

Dipartimento di Fisica e INFN Genova

Lab. Naz. INFN del Gran Sasso

Dipartimento di Fisica e INFN Milano

Dipartimento di Fisica e INFN Pavia

Dipartimento di Fisica e INFN Perugia

✓ Poland:

Jagellonian University Krakow

✓ Russia

JINR Dubna

Kurchatov Intitue - Moscow

✓ United States

Bell Laboratories, Lucent Technologies

Massachusetts Institute of Technology


Princeton University


Virginia Polytechnic Institute

Borexino

A real time, calorimetric, scintillation detector, for low energy solar neutrinos, under installation at the Gran Sasso underground Laboratory, aimed at the detection of the monoenergetic ${}^7\text{Be}$ neutrinos, through scattering off the electrons of the scintillator

Borexino Design





- BX > Tank for BOREXINO
- BB > Building for electronics equipments
- CTF > Counter Test Facility
- CR > Clean-Room for CTF
- S > Storage Area for Pseudocumene Scintillator
- H > Tunnel Section (Hall-C)
- W > Crane

Main Components: Detector

Scintillator

Nylon (Inner and Outer) Vessels

Buffer Liquid

Stainless Steel Sphere

support of PMT's

**containment of the buffer (zero
buoyancy for the nylon vessels)**

PMT's

Concentrators

Muon veto

Calibration equipments

Water Tank

Electronics and DAQ

Main components: Plants

Storage Vessels

Scintillator Purification systems

Water extraction

Distillation

Column purification

Nitrogen sparging

N₂ PLANT

Fluid Handling System

Water Purification System

Clean room

Scintillator

Solvent : Pseudocumene

Solute: PPO (1.5 g/l)

Light yield: 11000 ph/MeV

Att. Length (@420): 30 m

Scatt. length (@420 nm): 7 m

Decay Time (fast component) : 3.5 ns

Good α β properties

Photomultipliers

8" Electron Tubes Limited 9351 type

P/V : 2.5

Transit Time Spread: 1 ns

Dark Count rate: 1kHz

Afterpulsing < 3%

Low radioactive glass and internal parts

Light Concentrators

Truncated string cone design

Optimized to collect the light from the inner vessel and 20 cm beyond it

Material: anodized aluminum

Mesured quantities

The electronics measures and provides for each triggered event :

- the photomultipliers pulse height
⇒ energy measurement
- the photoelectrons arrival time
(0.3 ns resolution)
⇒ location identification
- the absolute time of the event

Expected detector performances

Effective Coverage: 30%

Photoelectron yield: 400 pe/MeV

Energy resolution (@ 1MeV): 5 %

Position resolution (@ 1 MeV): 10 cm

Calibrations

A variety of calibration and monitoring systems are planned:

✓ Laser pulses distributed to all PMT's with a fiber optics splitting system

- timing calibration

- gain adjustment via detection of the single photoelectron peak

✓ External sources (Th) located in the S.S.S close to the light cones

- check of the stability in time of the overall detector response

✓ Internal sources inside the scintillator

- position calibration

- energy calibration

- α/β PSD determination

Calibrations

✓ Laser beams with different wavelengths through the buffer and laser excitation of the scintillator

- stability monitoring of optical properties

✓ Blue LEDs on the external tank for the outer muon veto detector

✓ Active tags of trace impurities in the scintillator


- cross check of the absolute energy scale determination

- additional stability monitor

✓ Calibration of the overall detector response via a sub-MeV ν -source (^{51}Cr)

Neutrino Detection in Borexino

Detection through the scattering reaction



off the electrons of the scintillator

The high luminosity and high radiopurity of the scintillator lead to a low detection threshold: 250 keV.

It is possible to detect the recoil electrons produced by the monoenergetic (0.861 MeV) ${}^7\text{Be}$ ν .

Maximum recoil energy: 0.66 MeV

SSM prediction: 55 ev/d for 100 T F. V

The Borexino program

- First direct measurement of ${}^7\text{Be}$ flux

Expected rates (ev/d) in a F.V. of 100 T


| Recoil Energy window MeV | SSM | LMA | SMA | LOW | VO |
|--------------------------|------|---|--|--|---------------------------|
| | | $\Delta m^2 = 1.8 \times 10^{-5}$ eV ² $\sin 2\theta = 0.76$ | $\Delta m^2 = 5.4 \times 10^{-6}$ eV ² $\sin^2 \theta = 5.5 \times 10^{-3}$ | $\Delta m^2 = 7.9 \times 10^{-8}$ eV ² $\sin^2 \theta = 0.96$ | |
| 0.25 - 0.8 | 55.2 | 30.7 | 11.7 | 29.0 | |
| | | | | day/night effect | seasonal variation |

- Probing vacuum oscillations via seasonal variation of the flux

- In absence of other time variations, demonstration of the solar origin of the signal through the 7% variation due to the Earth-Sun distance variation during the year


- Background ~ 15 ev/d

BOREXINO




RATES - PRE SNO SITUATION (FOGLI ET AL.)

BOREXINO




DAY-NIGHT PRE-SNO SITUATION (FOGLI ET AL.)

BOREXINO





RATES - POST SNO SITUATION (FOGLI ET AL.)



Other capabilities

⇒ ^8B spectrum in the unique energy window 1.5-5 MeV

⇒ Antineutrino Science



Search for solar $\bar{\nu}_e$

Geophysical $\bar{\nu}_e$ from the Earth

$\bar{\nu}_e$ from Type II Supernovae

Long-baseline $\bar{\nu}_e$ from European reactors

Radiopurity of the scintillator

Main issue for the feasibility of the experiment

Purity requirements for ^{238}U and ^{232}Th in the range of 10^{-16} g/g

Laboratory measurements on small samples: $2-3 \times 10^{-15}$ g/g
mainly limited by impurities leached from the wall of the vessels

Needed a direct measurement on some tons of scintillator with a sensitivity level at least 5×10^{-16} g/g \rightarrow CTF

Further high sensitivity measurements performed with Neutron Activation Analysis

Achievements of CTF

1 - Demonstration of unprecedented purity levels

$$^{14}\text{C}/^{12}\text{C} = (1.94 \pm 0.09) \times 10^{-18}$$

$$^{232}\text{Th} < (4.4 \pm 1.5) \times 10^{-16}$$

$$^{238}\text{U} < (3.5 \pm 1.3) \times 10^{-16}$$

2 - Demonstration of the effectiveness of the planned purification methods for Borexino

Purity levels confirmed with Neutron Activation Analysis

$$^{238}\text{U} < 2 \times 10^{-16}$$

CTF has been recently reinstalled for quality control of the scintillator prior to detector filling

OTHER BACKGROUND ISSUES

- EXTERNAL BACKGROUND FROM DETECTOR COMPONENTS

→ PROPER SELECTION OF LOW RADIOACTIVE MATERIALS

- R_m EMANATION FROM PMT'S SYSTEM

→ EMANATION TESTS OF MATERIALS PLUS R_m BARRIER

- R_m AND $^{85}Kr_2$ IN THE SCINTILLATOR

→ SPARGING WITH ULTRAPURE N_2

$$R_m \sim 0.5 \mu Bq/m^3$$

- COSMOGENIC ACTIVITIES → MUON VETO

- DUST → CONSTRUCTIONS/INSTALLATIONS

UNDER CLEAN ROOM CONDITIONS

- SURFACE CONTAMINATIONS

→ PASSIVATION/ELECTROPOLISHING OF ALL

SURFACES EXPOSED TO SCINT. AND BUFFER

STATUS OF THE EXPERIMENT PREPARATION

SCINTILLATOR COMPONENTS (PC AND PPO):
MANUFACTURERS IDENTIFIED, CONTRACTS
FINALIZED, ON PURPOSE LOADING STATION
CONSTRUCTED AT THE COMPANY PLANT

NYLON (INNER AND OUTER) VESSELS: TEST
PROTOTYPES ALREADY PRODUCED, MATERIAL
SELECTION COMPLETED, WHOLE AMOUNT OF NYLON
EXTRUDED


STAINLESS STEEL SPHERE: CONSTRUCTION AND
SURFACE TREATMENTS COMPLETED


PMT'S: ALL DEVICES PRODUCED

50% INSTALLED ON THE SPHERE


SUITABLE TO BE IMMERSSED IN WATER

AND PSEUDOCUMENE









STATUS OF THE EXPERIMENT PREPARATION


WATER TANK: COMPLETED


ELECTRONICS AND DAQ: HARDWARE AND SOFTWARE READY, FINAL INTEGRATION IN PROGRESS

MUON VETO: DEDICATED PMT'S READY, ELECTRONIC IN PREPARATION

CONCENTRATORS: 80% PRODUCED, 50% INSTALLED

CALIBRATION EQUIPMENTS: FIBERS, EXTERNAL SOURCES EQUIPMENT, BUFFER MONITORING EQUIPMENTS INSTALLED ON THE TOP HEMISPHERE





STATUS OF THE EXPERIMENT CONSTRUCTION

STORAGE VESSELS : COMPLETED


SCINTILLATOR PURIFICATION SYSTEMS : IN
ADVANCED PHASE OF INSTALLATION, TEST
FORESEEN FROM SEPTEMBER WITH CTF


FLUID HANDLING SYSTEM : READY BY THE
FALL


CLEAN ROOM : CONSTRUCTED AND IN USE

FIRST DELIVERY OF PSEUDOCUMENE : 18 TONS
AT THE END OF AUGUST FOR TEST IN CTF

CTF (COUNTING TEST FACILITY) : RE-BUILT
AND PRESENTLY FILLED WITH WATER









CONCLUSIONS

MOST OF THE BOREXINO INSTALLATIONS
HAVE BEEN COMPLETED IN HALL C

ALL THE REMAINING EQUIPMENTS ARE
RAPIDLY APPROACHING THE INSTALLATION
PHASE

START-UP OF THE FILLING EXPECTED
WITHIN THE NEXT SPRING

CTF REBUILT, READY FOR QUALIFICATION OF
THE SCINTILLATOR AND FOR TEST OF THE
PURIFICATION SYSTEMS

THE BOREXINO DATA WILL BE THE FIRST
OUTCOME OF A REAL TIME INVESTIGATION OF
THE SUB-MEV SOLAR NEUTRINO REGION. THEY
WILL CONSTITUTE A POWERFUL DIAGNOSTIC
TOOL FOR THE LOW REGION